

Name of Manufacturer:

Abacus®

ABACUS LIGHTING LIMITED

Sutton - in - Ashfield, Nottinghamshire.

NG17 5FT ENGLAND

Tel: (+44) 01623 511111 Fax: (+44) 01623 552133

DATA SHEET No.

T107RLH

Page

1 of 2

Revision No

Date

9th JUNE 2005

NAME OF CONTRACT:

PART A

General

Column Reference

Column nominal height (m)

Column material

Material design strength N/mm sq.

No. of door openings


Door opening size

Height	<input type="text" value="406"/>	(mm)
Width	<input type="text" value="127"/>	(mm)

Height (mm)	Width (mm)	Depth (mm)
<input type="text" value="406"/>	<input type="text" value="145"/>	<input type="text" value="150"/>

Corrosion protection

Acceptable positions of bracket arms relative to door position



Manufacturers drawing ref. no:

Basic system type

Additional sacrificial steel thickness (mm)

Terrain Category as defined in EN40-3-1

Planting depth (m)

PART B

Foundation data

Relavent forces and moments at ground level.

Line of action of max moment relative to door opening

Standard Soil Type Factor G		
<input type="text" value="630"/>	<input type="text" value="390"/>	<input type="text" value="230"/>
***** (m)	***** (m)	0.264 (m)

Bolt hole centres	Hole diameter	Design load/bolt
<input type="text" value="300"/> (mm)	<input type="text" value="30"/> (mm)	<input type="text" value="33518"/> (N)

Moment (Nm) Shear (N)



(LOADINGS FOR COLUMN ARE UNFACTORED)

For flangeplates with slotted holes a diagram shall be included with this data sheet.

Details of Attachments	N/A
Area x Cf	(sq m) x
Height	(m)
Offset	(m)

Data Sheet No.	T107RLH
Revision	Page 2 of 2
Date	9th JUNE 2005

PART C
Acceptable Lanterns

Post Top Columns

Lantern Lever Arm (mm)	
Due to Wt. of Lantern	Due to Wind on Lantern
300	300

		Rationalized Wind Loading Factors			
Lantern Connection	Lantern	396	429	466	576
Diameter (mm)	Length (mm)	Max. Wt. (Kg)	Maximum windage area (sq.m) For Rationalized Wind Loading Factors		
AS REQUIRED	76*	0.608	0.553	0.503	0.4

Single Arm Bracket Column

*Max Headload - RLH1M = 40kg, RLH2M = 76kg

Lantern Lever Arm (mm)	
Due to Wt. of Lantern	Due to Wind on Lantern
500	500

Bracket Projection (m)	Bracket Reference	Material		Lantern Connection			Lantern Maximum Weight (Kg)	Maximum windage area (sq.m) For Rationalized Wind Loading Factors			
		Grade	Design Strength N/sq.mm	Fixing Angle	Diameter (mm)	Length (mm)					
0.5	BKT-05/S	S275	275	AS REQUIRED			12	0.247	0.224	0.203	0.16
1	BKT-10/S	S275	275	AS REQUIRED			12	0.167	0.15	0.135	0.103
1.5	BKT-15/S	S275	275	AS REQUIRED			12	0.114	0.101	0.089	0.063
2	BKT-20/S	S275	275	AS REQUIRED			12	0.067	0.056	*****	*****

Double Arm Bracket Column

Lantern Lever Arm (mm)	
Due to Wt. of Lantern	Due to Wind on Lantern
400	400

Bracket Projection (m)	Bracket Reference	Material		Lantern Connection			Lantern Maximum Weight (Kg)	Maximum windage area (sq.m) For Rationalized Wind Loading Factors			
		Grade	Design Strength N/sq.mm	Fixing Angle	Diameter (mm)	Length (mm)					
0.5	BKT-05/D	S275	275	AS REQUIRED			12	0.346	0.314	0.284	0.222
1	BKT-10/D	S275	275	AS REQUIRED			12	0.315	0.283	0.254	0.193
1.5	BKT-15/D	S275	275	AS REQUIRED			12	0.284	0.252	0.223	0.163
2	BKT-20/D	S275	275	AS REQUIRED			12	0.236	0.205	0.177	0.118

PART D
CERTIFICATION

It is certified that the information given in this data sheet has been obtained in accordance with the requirements of BS EN 40 as implemented by Departmental Standard BD 26 and the specification.

Signed on behalf of the Contractor

Date.....9th JUNE 2005.

ABACUS LIGHTING LTD

Sutton - in - Ashfield Nottinghamshire NG17 5FT Tel: (+44) 01623 511111 Fax: (+44) 01623 552133

PATENT No. 968113
 Copyright Strictly Reserved
 Abacus Municipal Ltd.
 ©1989

GENERAL TOLERANCES
 UNLESS STATED
 OTHERWISE:-
 0-500mm -----#5
 501mm-1000mm-----#10
 ABOVE-----#20


DATE 17/8/89
 SCALE 1:33.333
 CHECKED S WOOD
 DRAWN A.BOOTH

SALES ORDER No.
 T107RLH
 DETAIL OF T107RLH
 COLUMN

DRG. No. T107RLH
 CLIENT STANDARD COMPONENT
 SUTTON-IN-ASHFIELD, NOTTS
Abacus
 (R)

REV.	SIG.	DESCRIPTION	DATE	CHD.
C	AAT	SEE AMD NO 1772	28.1.95	SW
B	SDW	SEE AMD NO 1769	17.1.95	SW
A	A.B.	SEE AMD. NO. 1487	13/1/92	SW

ITEM NO. T107RLH
 WEIGHT = 166KG



MATERIAL	LENGTH	QTY
Ø114x3.0CHS	4265	1
Ø140x3.6CHS	4305	1

1. FIRST ANGLE PROJECTION

2. DIMENSIONS SHOWN IN BRACKETS THUS (25) ARE REF. DIMENSIONS ONLY.

3. REMOVE ALL BURRS AND SHARP EDGES.

4. DO NOT SCALE IF IN DOUBT ASK

5. WELDING SYMBOLS ARE TO BS 499

6. ALL STANDARDS AND SPECIFICATIONS ARE TO BE TO THE LATEST REVISIONS.

7. FILLET WELDS TO BE TO WELD PROCEDURE No. 031W.

8. CHS TO BS4360 GRD 50 WITH A MIN YIELD STRESS OF 355N/mm. sq AND A TENSILE STRENGTH OF 490N/mm. sq. PLATE TO BS4360 GRD 43A. PLATE 19mm THICK AND OVER TO BE CHARPY TESTED TO A VALUE OF 27J. AT -15°C.

9. FINISH: HOT DIP GALV TO BS729

10. BASE COMPARTMENT IS FITTED WITH A 1mm THICK TIMBER BASEBOARD MEASURING 1220 x 120 AND A M8 EARTHING SET. THE UPPER DOOR OPENING IS 578 x 165 AND IS COVERED BY THE LID OF THE COLUMN THE LOWER DOOR OPENING IS 406 x 127 AND IS COVERED BY A 2mm THICK PRESSED STEEL DOOR SECURED BY A TRIANGULAR HEADED ST. ST. SCREW

11. CABLE ENTRY SLOT MEASURES 150 x 50

12. ALL TIMBER COMPONENTS TO BE CREOSOTED.

13. FOR DETAILS OF SHAFT JOINT SEE DRG. NO. C201/47


14. FOR DETAILS OF 219 R/L. BASE SEE DRG. NO. RL201/11 SERIES





NOTES

1. FIRST ANGLE PROJECTION.



2. DIMENSIONS SHOWN IN BRACKETS THUS (25) ARE REF. DIMENSIONS ONLY.

3. REMOVE ALL BURRS AND SHARP EDGES.

4. DO NOT SCALE IF IN DOUBT ASK.

5. WELDING SYMBOLS ARE TO BS EN 24063 & BS EN 22553.

6. ALL STANDARDS AND SPECIFICATIONS ARE TO BE TO THE LATEST REVISIONS.

7. FILLET WELDS TO BE TO WELD PROCEDURE No. 031W.

8. CHS TO BS EN 10210 GRD S355 WITH A TENSILE STRENGTH OF 490N/mm.sq. PLATE TO BS EN 10025 GRD S275. PLATE 25mm THICK AND OVER TO BE CHARPY TESTED TO A VALUE OF 27J. AT -20 °C.

9. FINISH: HOT DIP GALV TO BS EN ISO 1461.


10. BASE COMPARTMENT IS FITTED WITH A 11mm THICK TIMBER BASEBOARD MEASURING 1220 x 120 AND A M8 EARTHING SET. THE UPPER DOOR OPENING IS 578 x 165 AND IS COVERED BY THE LID OF THE COLUMN. THE LOWER DOOR OPENING IS 406 x 127 AND IS COVERED BY A 2mm THICK PRESSED STEEL DOOR SECURED BY A TRIANGULAR HEADED ST. ST. SCREW.

11. FLANGE PLATE IS TYPE '2' TO DRG. NO. C201/22.

12. ALL TIMBER COMPONENTS TO BE CREOSOTED.

13. FOR DETAILS OF SHAFT JOINT SEE DRG. NO. C201/47.

14. FOR DETAILS OF 219 R/L. BASE SEE DRG. NO RL201/11 SERIES.



ITEM NO: T107RLH/FP
WEIGHT: 145 KG.

MATERIAL	LENGTH	QTY
Ø114X3.0THK CHS	4265	1
Ø140X3.6THK CHS	4305	1

REV:	SIG:	DESCRIPTION	DATE	CHD.
C	A.T.	SEE AMD. No. 1772.	28.01.95	
B	SDW	SEE AMD. No. 1769.	17.01.95	S.W.
A	A.B.	SEE AMD. No. 1487.	13.11.92	S.W.

Copyright Strictly Reserved
Abacus Municipal Ltd.
© 1989

GENERAL TOLERANCES
UNLESS STATED
OTHERWISE: -

0-500mm----- ±5
501mm-1000mm--- ±10
ABOVE----- ±20

DRAWN A. BOOTH.
CHECKED S. WOOD.
SCALE DO NOT SCALE
DATE 17.08.89.

TITLE
DETAIL OF T107RLH/FP COLUMN.

SALES ORDER No.

Abacus[®]
SUTTON-IN-ASHFIELD, NOTTS

CLIENT STANDARD COMPONENT

DRG. No. T107RLH/FP C

PATENT No. 968113
REG. DESIGN No.